



## ADDENDUM No. 2

**DATE:** October 4, 2019  
**TO:** All Bidders  
**FROM:** Regional Capital Assistance Team (RCAT), Taunton Housing Authority  
**PROJECT:** **Window Panel Insulation** at Riddell Road, 667-2  
**DHCD FISH#:** 083047      Projectdog Code: 834989  
**LHA:** East Bridgewater Housing Authority, East Bridgewater MA

---

Bidders are hereby informed that Plans and Specifications for the above-referenced project are modified, corrected and/or supplemented by this Addendum, which shall become a part of the Contract Documents prepared by the Southeast Regional Capital Assistance Team (RCAT). All Bidders are instructed to acknowledge all the Addenda issued in Paragraph B on the Form for Quotes. **Failure to do so shall result in the rejection of your bid.**

Specified insulation material is changed from closed-cell spray foam insulation to stone wool insulation board. In order to provide bidders time to adjust their bids, the due date for Quotes is changed. Therefore, the bidding documents are hereby modified as follows:

1. Specification **Section 00.11.10 – Public Notification for Written Quotes:** Fifth paragraph from the top beginning with “Written Quotes will be received until”. **DELETE** “10:00 a.m., Wednesday, October 9, 2019.” **REPLACE WITH** “10:00 a.m., Friday, October 11, 2019.”
2. Specification **Section 07.20.00 – Building Insulation & Moisture Protection:**
  - a. Item 1.2.A.1: **DELETE** entire sentence. **REPLACE WITH** “Stone wool insulation board at interior wall infills.”
  - b. Item 2.1.A: **DELETE** entire paragraph. **REPLACE WITH:**

“Stone wool insulation: Rigid, high-density, non-combustible, moisture resistant, vapor permeable, non-structural exterior mineral stone wool insulation sheathing designed for rain screen/cavity wall applications such as Rockwool ComfortBoard 110, Owens Corning Thermafiber RainBarrier HD, Johns Manville JM CladStone 60 Water & Fire Block Insulation, or approved equal.

    1. Minimum R-Values: R-4 per inch of thickness.
    2. 3 inch manufactured thickness.”
3. Drawing **A1-02, Detail 3:** **DELETE** note reading “SPRAY FOAM INSULATION, FILL ALL VOIDS BETWEEN STUDS AND BEHIND FRAMING TO FACE OF EXISTING PANEL WITHOUT GAPS”.  
**REPLACE WITH:** “STONE WOOL INSULATION, FILL ALL SPACES BETWEEN STUDS AND ENTIRE CAVITY BETWEEN STUDS AND FACE OF EXISTING METAL PANEL WITHOUT GAPS OR VOIDS”.

All other portions of the Contract Documents remain unchanged. The date, time and place Quotes are due remain unchanged.

**End of Addendum No. 2**